# CITY OF BELLINGHAM, PUBLIC WORKS DEPARTMENT SQUALICUM CREEK RE-ROUTE PROJECT PHASES I and II

Bellingham, Washington



CITY OF BELLINGHAM, PUBLIC WORKS DEPT. 210 LOTTIE ST. BELLINGHAM, WA 98225 360.778.7900



501 Portway Ave, Suite 101 HOOD RIVER, OR 97031 541.386.9003 www.interfluve.com





# DRAWING INDEX


BY INTER-FLUVE: RE-ROUTE CHANNEL


1. COVER, VICINITY MAP, SHEET INDEX 2. GENERAL NOTES 3 SWPPP 4. SWPPP DETAILS 6. PROJECT OVERVIEW
7. CONSTRUCTION SEQUENCE, PHASE I
8. CONSTRUCTION SEQUENCE, PHASE II 9. PHASE I GRADING PLAN: STA 0+00 (BUG LAKE) TO 4+00 (I-5) 10. PHASE I GRADING PLAN: STA 6+00 (I-5) TO 13+50 11. PHASE I GRADING PLAN: STA 13+50 TO 21+00 12. PHASE I GRADING PLAN: STA 21+00 TO 25+00 (JAMES ST) 13. PHASE I CROSS SECTIONS

14. PHASE I CROSS SECTIONS AND TYPICAL CHANNEL DIMENSIONS

15. PHASE II GRADING PLAN: STA 25+00 (JAMES ST) TO 32+50

16. PHASE II GRADING PLAN: STA 32+50 TO 39+00 17. PHASE II GRADING PLAN: STA 39+00 TO 46+00 18. PHASE II GRADING PLAN: STA 46+00 TO 51+50 (TIE IN) 19. PHASE II CROSS SECTIONS AND TYPICAL CHANNEL DIMENSIONS 20. PHASE II CROSS SECTIONS 21. SIDE CHANNEL 1 GRADING PLAN 22. SIDE CHANNEL 2 GRADING PLAN
23. SIDE CHANNEL 3 GRADING PLAN
24. SIDE CHANNEL 4 GRADING PLAN 25. CHANNEL DETAILS 27. FILL SQUALICUM CREEK AT SUNSET POND INLET 28. FILL TRIB W SCOUR POOLS 29. FILL CHANNELS (PHASE 1) BY KPFF: 30. HORIZONTAL CONTROL PLAN 1 31. HORIZONTAL CONTROL PLAN 2 32. INTERIM BERM SITE PREP AND EROSION CONTROL PLAN 1
33. INTERIM BERM SITE PREP AND EROSION CONTROL PLAN 2
34. INTERIM BERM SITE PREP AND EROSION CONTROL PLAN 3 35. INTERIM BERM DETAILS





DIR. PUBLIC WORKS\_

CITY ENGINEER\_

OPER. ENGINEER



**ENGINEER** 

CONTACT PERSON:

BELLINGHAM

WASHINGTON

E BAKERVIEW RD.

RAILROAD

INTERSTATE 5

PROJECT LOCATION

E. ILLINOIS ST.

PROJECT VICINITY MAP

ORCHARD DR.

SÉATTLE

PROJECT ENGINEER DESIGNED/DRAWN \_ MRM INSPECTOR

PROJECT ENGINEER AT 778-7900

CITY OF BELLINGHAM. WASHINGTON PUBLIC WORKS DEPARTMENT ENGINEERING DIVISION

SCALE Horiz. Vert.

NAD83/91 NAVD88

Date 04/30/15 Field Bk.\_

36. INTERIM BERM TYPICAL SECTIONS

44. CULVERT BERM DETAILS

37. INTERIM BERM PLAN AND PROFILE 1
38. INTERIM BERM PLAN AND PROFILE 2 39. INTERIM BERM PLAN AND PROFILE 3 40. INTERIM BERM PLAN AND PROFILE 4 41. INTERIM BERM PLAN AND PROFILE 5

> SQUALICUM CREEK RE-ROUTE HABITAT ENHANCEMENT PROJECT **COVER SHEET**

THE CONTRACTOR SHALL ATTEND PRECONSTRUCTION CONFERENCES WITH THE CITY OF BELLINGHAM PRIOR TO BEGINNING CONSTRUCTION.

ALL WORK SHALL CONFORM TO THE CURRENT EDITIONS OF STANDARD PLANS AND SPECIFICATIONS OF THE WASHINGTON STATE DEPARTMENT OF TRANSPORTATION (WSDOT), AND CITY OF BELLINGHAM STANDARDS UNLESS INDICATED OTHERWISE BY THE CONTRACT DOCUMENTS. IN CASE OF A CONFLICT BETWEEN THE REGULATORY STANDARDS OR SPECIFICATIONS, THE MORE STRINGENT WILL PREVAIL.

#### IN-WATER WORK PERIODS

IN-WATER WORK SHALL OCCUR DURING THE PERMITTED WORK PERIOD STATED IN THE HYDRAULIC PROJECT APPROVAL AND NATIONWIDE PERMIT: JULY 1 THROUGH OCTOBER 15, 2015. SEE APPENDIX IN SPECIFICATIONS DOCUMENT.

#### FXISTING DATA

ELEVATIONS ARE RELATIVE TO CITY OF BELLINGHAM DATUM (NAVD88).

#### UTILITIES

UNDERGROUND UTILITIES ARE KNOWN TO EXIST IN THE AREA OF CONSTRUCTION. THE LOCATION OF EXISTING UTILITIES SHOWN IS APPROXIMATE. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO CONTACT ALL UTILITY OWNERS FOR LOCATIONS AND TO FIELD VERIFY ALL UTILITY LOCATIONS PRIOR TO CONSTRUCTION. THE ONE—CALL NUMBER FOR UNDERGROUND UTILITIES IS 1—800—424—5555.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE INTEGRITY OF ALL EXISTING UTILITIES THROUGHOUT CONSTRUCTION.

IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO PROMPTLY NOTIFY THE CITY OF ANY CONFLICT WITH EXISTING UTILITIES.

ALL EXISTING FACILITIES, LANDSCAPE IMPROVEMENTS, AND UTILITIES NOT SPECIFICALLY IDENTIFIED FOR REMOVAL SHALL BE PROTECTED THROUGHOUT CONSTRUCTION OR RESTORED AT COMPLETION OF THE WORK.

#### SOILS

SURFACE AND SUBSURFACE CONDITIONS WERE EXPLORED AND SAMPLED BY GEO-ENGINEERS, INC. RESULTS INCLUDING SOIL CHARACTERIZATION AND GROUNDWATER LEVELS, SOIL REPORTS ARE ATTACHED TO THE PROJECT SPECIFICATIONS.

#### CONSTRUCTION ACCESS/TRAFFIC CONTROL

THE CONTRACTOR SHALL PROVIDE A TRAFFIC CONTROL PLAN TO THE CITY FOR REVIEW. CONSTRUCTION SHALL NOT COMMENCE UNTIL APPROVAL. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR IMPLEMENTING REQUIRED TRAFFIC CONTROL AS REVIEWED AND APPROVED BY DWNER'S REPRESENTATIVE

THE CONTRACTOR IS SOLELY RESPONSIBLE FOR PROVIDING ALL REQUIRED TRAFFIC CONTROL INCLUDING, BUT NOT LIMITED TO, SIGNAGE AND FLACCEDS

ALL EQUIPMENT, MATERIALS AND PERSONNEL SHALL REMAIN WITHIN THE LIMITS OF DISTURBANCE.

THE CONTRACTOR SHALL KEEP THE WORK AREAS IN A CLEAN AND NEAT CONDITION FREE OF DEBRIS AND LITTER FOR THE DURATION OF THE PROJECT.

ALL EFFECTED AREAS INCLUDING ROADS AND ACCESS ROUTES SHALL BE RESTORED TO ORIGINAL CONDITION OR BETTER.

ALL DISTURBED AREAS OUTSIDE THE LIMITS OF DISTURBANCE SHALL BE RESTORED TO ORIGINAL CONDITION OR BETTER AT NO COST TO THE OWNER.

#### CONSTRUCTION STAKING

CONTRACTOR SHALL PROVIDE STAKING OF PROJECT LIMITS, CHANNEL CENTERLINE, EXTENTS OF FILL AREAS.

CONTRACTOR SHALL MEET WITH THE OWNER'S REPRESENTATIVE TO DEFINE AND MARK LIMITS OF DISTURBANCE PRIOR TO MOBILIZATION OF EQUIPMENT OR MATERIALS ONTO THE SITE.

THE CONTRACTOR SHALL REPLACE DAMAGED OR DESTROYED CONSTRUCTION STAKES AT NO COST TO THE OWNER. CONSTRUCTION MATERIALS

EARTHWORK VOLUMES ARE THE DIFFERENCE BETWEEN DESIGN GROUND AND SURVEYED GROUND.
LOCATION, ALIGNMENT, SIZE, AND ELEVATION OF LOGS AND LOGS WITH ROOT WADS ARE SUBJECT TO CHANGE BASED ON FIELD
CONDITIONS, AND MATERIAL SIZE.

ANY EXCESS MATERIALS SHALL BE STOCKPILED NEATLY WITHIN THE LIMITS OF DISTURBANCE OR OTHER APPROVED STOCKPILE AREA. THE MATERIAL SHALL BE REMOVED FROM THE SITE PRIOR TO THE COMPLETION OF WORK.

#### CONSTRUCTION DEWATERING

CONTRACTOR SHALL PERFORM CONSTRUCTION DEWATERING IN SUCH A MANNER AS TO PREVENT THE RELEASE OF SEDIMENT-LADEN WATER TO SURFACE WATERS. SEDIMENT LADEN WATER MAY BE ALLOWED TO SHEET FLOW THROUGH NON-WETLAND FORESTED AREAS BEFORE INFILTRATING INTO THE GROUND. THIS METHOD IS TYPICALLY USED WHERE THEAT TO FISH HABITATS IS SMALL, USUALLY AWAY FROM STREAMS. IN MORE SENSITIVE ENVIRONMENTS, A "DIRT-BAG" OR SEDIMENT RETENTION STRUCTURE SHALL BE REQUIRED.

THE CONTRACTOR IS ADVISED THAT THE PROJECT AREA DRAINS TO A SALMON BEARING STREAM AND/OR STATE WATERS AND THAT THE CONTRACTOR IS RESPONSIBLE TO PROTECT THE RECEIVING WATERS FROM DELETERIOUS EFFECTS OF CONSTRUCTION.

THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING THE EROSION CONTROL MEASURES SHOWN OR DESCRIBED IN THE CONTRACT DOCUMENTS AND ANY ADDITIONAL MEASURES THAT MAY BE REQUIRED BY THE CONTRACTORS MEANS AND METHODS OF CONSTRUCTION AS NEEDED TO CONTROL EROSION AND SEDIMENT AT THE CONSTRUCTION SITE AND TO PREVENT VIOLATION OF SURFACE WATER QUALITY, GROUND WATER QUALITY, OR SEDIMENT MANAGEMENT STANDARDS.

#### VEHICLE OPERATIONS AND STAGING

VEHICLE CLEANING, MAINTENANCE, REFUELING, AND FUEL STORAGE SHALL OCCUR IN DESIGNATED STAGING AREAS THAT ARE 100 FEET OR MORE FROM ANY STREAM, WATER BODY OR WETLAND.

THE CONTRACTOR SHALL DIAPER ALL STATIONARY POWER EQUIPMENT (I.E. GENERATORS, PUMPS, CRANES) OPERATED WITHIN 100 FEET OF ANY STREAM, WATER BODY OR WETLAND TO PREVENT LEAKS, UNLESS SUITABLE CONTAINMENT IS PROVIDED TO PREVENT POTENTIAL SPILLS FROM ENTERING ANY STREAM OR WATER BODY.

THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING A SPILL CONTAINMENT AND CONTROL PLAN WITH NOTIFICATION PROCEDURES. SPECIFIC CLEANUP AND DISPOSAL INSTRUCTIONS FOR DIFFERENT PRODUCTS. THE CONTRACTOR SHALL STAGE QUICK RESPONSE CONTAINMENT AND CLEANUP MEASURES ON THE SITE, ALONG WITH PERSONEL TRAINED IN PROPOSED METHODS FOR DISPOSAL OF SPILLED MATERIALS AND SPILL CONTAINMENT.

CONTRACTOR SHALL INSPECT ALL VEHICLES OPERATED WITHIN 150 FEET OF ANY STREAM, WATER BODY OR WETLAND DAILY FOR FLUID LEAKS BEFORE LEAVING THE VEHICLE STAGING AREA. REPAIR ANY LEAKS DETECTED IN THE VEHICLE STAGING AREA BEFORE THE VEHICLE RESUMES OPERATION. DOCUMENT INSPECTIONS IN A RECORD THAT IS AVAILABLE FOR REVIEW UPON REQUEST.

BEFORE OPERATIONS BEGIN AND AS OFTEN AS NECESSARY DURING OPERATION, PRESSURE WASH ALL EQUIPMENT THAT WILL BE USED BELOW BANKFULL ELEVATION UNTIL ALL VISIBLE EXTERNAL OIL, GREASE, MUD, AND OTHER VISIBLE CONTAMINANTS ARE REMOVED.

WHEN TRUCKING SATURATED SOILS FROM THE SITE, WATERTICHT TRUCKS MUST BE USED, OR LOADS SHALL BE DRAINED ON—SITE SO THAT WATER SEEPING FROM THE SOIL CANNOT DRAIN FROM THE VEHICLE. ALL VEHICLES LEAVING THE SITE SHALL HAVE TIRES CLEANED AT A TRUCK WASHING STATION.

STABILIZED CONSTRUCTION ENTRANCE (EXIT) AND TIRE WASH SHALL BE INSTALLED AT EACH LOCATION WHERE HIGHWAY HAULERS WILL LEAVE THE SITE ONTO PAVED ROADS.
FROSION CONTROL

PUBLIC RIGHTS OF WAY ARE TO BE KEPT IN A CLEAN AND SERVICEABLE CONDITION AT ALL TIMES. IN THE EVENT MATERIALS ARE INADVERTENTLY DEPOSITED ON ROADWAYS IT SHALL BE REMOVED PROMPTLY. MATERIALS SHALL BE SWEPT AND REMOVED PRIOR TO ANY STREET FLUSHING. PUBLIC AND PRIVATE DRAINAGE AND WATER WAYS ARE TO BE PROTECTED FROM POLLUTION.

CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING AND MAINTAINING ALL NECESSARY EROSION CONTROL FACILITIES TO COMPLY WITH APPLICABLE EROSION CONTROL REGULATIONS.

THE CONTRACTOR SHALL ENSURE THAT MATERIALS FOR EMERGENCY EROSION CONTROL ARE ONSITE, INCLUDING BUT NOT LIMITED TO: SEDIMENT CONTROL MATERIALS (I.E. SILT FENCE, STRAW BALES, STRAW WATTLES, DIRT BAGS); AN OIL-ABSORBING, FLOATING BOOM WHENEVER FLOWING SURFACE WATER IS PRESENT.

THE CONTRACTOR SHALL SHALL IMPLEMENT MEASURES TO CONTROL AND MINIMIZE WIND-BLOWN DUST FROM THE SITE.

THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR PROVIDING EROSION, SEDIMENT, AND POLLUTION CONTROL MEASURES TO COMPLY WITH ALL APPLICABLE REGULATIONS. NOTICE TO PROCEED WILL NOT BE ISSUED UNTIL THE CONTRACTOR OBTAINS AN APPROVED ESC PLAN.

THE CONTRACTOR SHALL SUBMIT NAME, ADDRESS AND 24—HOUR PHONE NUMBER OF PERSON RESPONSIBLE FOR EROSION PREVENTION AND SEDIMENT CONTROL MEASURES, AND SPILL CONTAINMENT.

THE IMPLEMENTATION OF EROSION, SEDIMENT, AND POLLUTION CONTROL MEASURES AND THE CONSTRUCTION, MAINTENANCE, REPLACEMENT, AND UPGRADING OF THESE FACILITIES IS THE RESPONSIBILITY OF THE CONTRACTOR UNTIL ALL CONSTRUCTION IS COMPLETED AND APPROVED. AND VEGETATION IS FSTABLISHED.

THE BOUNDARIES OF THE CLEARING LIMITS SHOWN ON THIS PLAN WILL BE FLAGGED IN THE FIELD PRIOR TO CONSTRUCTION BY THE OWNER'S REPRESENTATIVE. DURING THE CONSTRUCTION PERIOD, NO DISTURBANCE BEYOND THE FLAGGED CLEARING LIMITS SHALL BE PERMITTED. THE FLAGGING SHALL BE MAINTAINED BY THE CONTRACTOR FOR THE DURATION OF CONSTRUCTION.

EROSION, SEDIMENT, AND POLLUTION CONTROL MEASURES MUST BE IMPLEMENTED PRIOR TO ANY GROUND DISTURBING ACTIVITY ON THE PROJECT SITE, AND IN SUCH A MANNER AS TO ENSURE THAT SEDIMENT AND SEDIMENT LADEN WATER DO NOT LEAVE THE PROJECT SITE, ENTER THE DRAINAGE SYSTEM OR ROADWAYS, OR VIOLATE APPLICABLE WATER STANDARDS.

DURING THE CONSTRUCTION PERIOD, EROSION, SEDIMENT, AND POLLUTION CONTROL MEASURES SHALL BE UPGRADED AS NEEDED FOR STORM EVENTS AND TO ENSURE THAT SEDIMENT AND SEDIMENT-LADEN WATER DO NOT LEAVE THE SITE.

DURING CONSTRUCTION, THE CONTRACTOR SHALL MONITOR INSTREAM TURBIDITY AND INSPECT ALL EROSION CONTROLS DAILY DURING THE RAINY SEASON AND WEEKLY DURING THE DRY SEASON, OR MORE OFTEN AS NECESSARY, TO ENSURE THE EROSION CONTROLS ARE WORKING ADEQUATELY. IF MONITORING OR INSPECTION SHOWS THAT THE EROSION CONTROLS ARE INEFFECTIVE, MOBILIZE WORK CREWS IMMEDIATELY TO MAKE REPAIRS, INSTALL REPLACEMENTS, OR INSTALL ADDITIONAL CONTROLS AS NECESSARY. THE CONTRACTOR SHALL REMOVE SEDIMENT FROM EROSION CONTROLS ONCE IT HAS REACHED 1/3 OF THE EXPOSED HEIGHT OF THE CONTROL.

A STABILIZED TEMPORARY CONSTRUCTION EXIT IS REQUIRED AT THE EACH CONSTRUCTION ACCESS POINT FROM THE STREET. THE FACILITY SHALL BE MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES MAY BE REQUIRED TO ENSURE THAT STREETS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT.

FROM MAY 1 - SEPT 30 NO SUBSTANTIALLY UNWORKED SOILS SHALL REMAIN EXPOSED FOR MORE THAN SEVEN DAYS AT A TIME.

CAUTION!!!

OVERHEAD AND UNDERGROUND
UTILITIES ARE KNOWN TO
EXIST IN AREA. NOT ALL ARE
SHOWN IN PLANS.

CALL UULC BEFORE YOU DIG. 2 BUSINESS DAYS ADVANCE NOTICE. (800) 424-5555

#### IN-CHANNEL WORK

THE MAJORITY OF THE WORK WILL OCCUR OUTSIDE OF THE ACTIVE WATERWAY. THEREFORE, CREEK DIVERSION AND DEWATERING SHALL OCCUR FOR THE PERIOD OF IN-CHANNEL WORK ONLY. IN-CHANNEL WORK INCLUDES DIVERTING SQUALICUM CREEK FROM SUNSET POND TO THE RE-ROUTE CHANNEL, OPENING THE RE-ROUTE CHANNEL, DEWATERING TRIB W, AND PLUGGING EXISTING INLET AND OUTLET OF SUNSET POND.

IN-CHANNEL WORK SHALL BE ISOLATED BY TEMPORARY DAMS INSTALLED UPSTREAM AND DOWNSTREAM OF WORK AREAS.

DEWATERING OF IN-CHANNEL WORK AREAS SHALL OCCUR CONCURRENT WITH FISH RESCUE. CONTRACTOR SHALL COORDINATE WITH THE CITY TO SCHEDULE WASHINGTON CONSERVATION CORP (WCC) FOR FISH RESCUE (MON - THUR). CONTRACTOR SHALL PROVIDE WCC AMPLE TIME TO SCHEDULE FISH RESCUE. IF DIVERSION FAILS DUE TO CONTRACTOR NEGLIGENCE, FISH RESCUE SHALL BE REPEATED BY WCC CREWS AT CONTRACTOR'S EXPENSE.

IF ADDITIONAL PUMPING IS REQUIRED TO DEWATER DURING CONSTRUCTION, PUMPED DISCHARGE SHALL RELEASE SEDIMENT—LADEN WATER IN A MANNER THAT DOES NOT CAUSE CONTAMINATION OR INCREASE TURBIDITY OF SURFACE WATERS. (SEE CONTROL DEWATERING).

PUMPS SHALL CONFORM TO LOCAL CODES FOR NOISE STANDARDS. PUMPS SHALL RUN
24 HRS PER DAY UNTIL CONSTRUCTION IS COMPLETED. CONTRACTOR SHALL PROVIDE BACK UP PUMPS. PUMP INTAKE SCREENS SHALL
MEET NMFS CRITERIA. SEE http://swr.nmfs.nooa.gov/hcd/pumpcrit.htm

TRIB W DIVERSION SHALL HAVE FLOW CAPACITY OF 1 CFS (450 GPM) OR GREATER.

#### FISH RESCUE

FISH BARRIERS SHALL BE PROVIDED AND INSTALLED UPSTREAM AND DOWNSTREAM OF THE PROJECT WHERE DESIGNATED IN THE PLANS

CONTRACTOR SHALL PROVIDE PUMPS FOR FISH RESCUE AND DEWATERING.

INITIAL CHANNEL DEWATERING SHALL OCCUR SLOWLY BY INCREMENTALLY REDUCING STREAM FLOWS OVER A PERIOD OF 30 MINUTES TO ALLOW TIME FOR FISH TO VOLITIONALLY MOVE DOWNSTREAM OR FIND RESIDUAL POOLS WITHOUT RISK OF SUDDEN STRANDING.

RESIDUAL POOLS WITHIN THE DEWATERED CONSTRUCTION SITE SHALL BE PUMPED DRY USING SCREENED PUMP INTAKES. RESIDUAL DEWATERING PUMP INTAKES SHALL ADHERE TO NMFS SCREENING CRITERIA. NATIONAL MARINE FISHERIES SERVICE JUVENILE FISH SCREEN CRITERIA (REVISED FEBRUARY 16, 1995) AND ADDENDUM: JUVENILE FISH SCREEN CRITERIA FOR PUMP INTAKES (MAY 9, 1996). SEE http://swr.nmfs.noog.gov/hcd/pumpcrit.htm

FISH REMOVAL TO BE PERFORMED BY WASHINGTON CONSERVATION CORPS CREWS AND COORDINATED THROUGH THE CITY.

#### ABBREVIATIONS

APPROX: APPROXIMATE
CFS: CUBIC FEET PER SECOND
GPM: GALLONS PER MINUTE

LBS: POUNDS
MIN: MINIMUM

MAX: MAXIMUM FT: FEET

LF: LINEAR FEET

SF: SQUARE FEET SY: SQAURE YARDS

CY: CUBIC YARDS

AC: ACRES

OC: ON CENTER
PLS: PURE LIVE SEED

CL: CENTERLINE

XS: CROSS SECTION

XS: CROSS SECTION

AVE: AVERAGE OR AVENUE

ST: STREET NTS: NOT TO SCALE

CS: CONTROL SUVERY

CSRPC: CONTROL SURVEY RED PLASTIC CAP

DISC: SURFACE MONUMENT DISC

CSHT: CHECK SHOT

LT: LEFT RT: RIGHT

N: NORTHING

E: EASTING

PI: POINT OF INTERSECTION
PVI: POINT OF VERTICAL INTERSECTION

PC: POINT OF CURVATURE

PT: POINT OF TANGENCY

SSMH: SANITARY SEWER MANHOLE TRIB: TRIBUTARY

TRIB. TRIBOTI

LWD: LARGE WOODY DEBRIS

WS: WATER SURFACE RR: RAILROAD NB: NORTHBOUND

SB: SOUTHBOUND CNG: CASCADE NATURAL GAS

HVF: HIGH VISIBILITY FENCE TESC: TEMPORARY EROSION AND SEDIMENT

CONTROL

SWPPP: STORMWATER POLLUTION PREVENION PLAN

COB: CITY OF BELLINGHAM

WCC WASHINGTON CONSERVATION CORPS

WSDOT: WASHINGTON STATE DEPARTMENT OF TRANSPORATION

B2B: BAY TO BAKER

PSE: Pacific Surveying & Engineering

TYP: TYPICAL
EL: ELEVATION
IE: INVERT ELEVATION

REINF: REINFORCED CONC; CONCRETE EXIST: EXISTING



inter-fluve

PROJECT ENGINEER MRM
DESIGNED/DRAWN MRM
INSPECTOR -

DIR. PUBLIC WORKS\_

CITY ENGINEER\_

OPER, ENGINEER.

TC

RAR

CITY OF BELLINGHAM, WASHINGTON PUBLIC WORKS DEPARTMENT ENGINEERING DIVISION SCALE
Horlz. \_\_\_\_\_
Vert. \_\_\_\_

SQUALICUM CREEK RE-ROUTE HABITAT ENHANCEMENT PROJECT GENERAL NOTES

#### ELEMENT 1 - MARK CLEARING LIMITS

PRIOR TO BEGINNING LAND DISTURBING ACTIVITIES, INCLUDING CLEARING AND GRADING, ALL CLEARING LIMITS, SENSITIVE AREAS AND THEIR BUFFERS, AND TREES THAT ARE TO BE PRESERVED WITHIN THE CONSTRUCTION AREA SHOULD BE CLEARLY MARKED, BOTH IN THE FIELD AND ON THE PLANS, TO PREVENT DAMAGE AND OFFSITE IMPACTS. PLASTIC, METAL, OR STAKE WIRE FENCE MAY BE USED TO MARK THE CLEARING

SUGGESTED BMP'S/BMP'S TO BE USED:

- . CLEARING LIMITS ARE WITHIN THE DEVELOPED ROAD PRISM AND INDICATED ON THE CONSTRUCTION SITE PLANS. LIMITS WILL BE MARKED IN THE FIELD BY THE CONTRACTOR.

  • BMP C103: HIGH VISIBILITY PLASTIC OR METAL FENCE.

#### ELEMENT 2 - ESTABLISH CONSTRUCTION ACCESS

(A) CONSTRUCTION VEHICLE ACCESS AND EXIT SHALL BE LIMITED TO ONE ROUTE IF POSSIBLE.

(B) ACCESS POINTS SHALL BE STABILIZED WITH QUARRY SPALL OR CRUSHED ROCK TO MINIMIZE THE TRACKING OF SEDIMENT ONTO PUBLIC

(C) WHEEL WASH OR TIRE BATHS SHOULD BE LOCATED ON-SITE, IF APPLICABLE.

(D) PUBLIC ROADS SHALL AT A MINIMUM BE CLEANED THOROUGHLY AT THE END OF EACH DAY. SEDIMENT SHALL BE REMOVED FROM ROADS BY SHOVELING OR PICKUP SWEEPING AND SHALL BE TRANSPORTED TO A CONTROLLED SEDIMENT DISPOSAL AREA. STREET WASHING WILL BE ALLOWED ONLY AFTER SEDIMENT IS REMOVED IN THIS MANNER.

(E) STREET WASH WASTEWATER SHALL BE CONTROLLED BY PUMPING BACK ON-SITE, OR OTHERWISE BE PREVENTED FROM DISCHARGING INTO SYSTEMS TRIBUTARY TO STATE SURFACE WATERS.

SUGGESTED BMP'S/BMP'S TO BE USED:

- BMP C106: WHEEL WASH
- BMP C107: CONSTRUCTION ROAD/PARKING AREA STABILIZATION

#### ELEMENT 3 - CONTROL FLOW RATES

(A) PROPERTIES AND WATERWAYS DOWNSTREAM FROM DEVELOPMENT SITES SHALL BE PROTECTED FROM EROSION DUE TO INCREASES IN THE VOLUME, VELOCITY, AND PEAK FLOW RATE OF STORMWATER RUNOFF FROM THE PROJECT SITE, PROPERTIES SUBJECT TO MINIMUM REQUIREMENT # 5 AND/OR #7 SHALL IMPLEMENT CONTROLS AS EARLY IN THE DEVELOPMENT AS IS PRACTICABLE TO MITIGATE FOR FLOW RATES.

(B) DOWNSTREAM ANALYSIS IS NECESSARY IF CHANGES IN FLOWS COULD IMPAIR OR ALTER CONVEYANCE SYSTEMS. STREAM BANKS. BED SEDIMENT OR AQUATIC HABITAT. SEE THE ECOLOGY MANUAL FOR OFFSITE ANALYSIS GUIDANCE.

(C) WHERE NECESSARY TO COMPLY WITH MINIMUM REQUIREMENT #7, STORMWATER RETENTION/DETENTION FACILITIES SHALL BE CONSTRUCTED AS ONE OF THE FIRST STEPS IN GRADING, DETENTION FACILITIES SHALL BE FUNCTIONAL PRIOR TO CONSTRUCTION OF SITE IMPROVEMENTS (F.G.

(D.) IF PERMANENT INFILTRATION PONDS ARE USED FOR FLOW CONTROL DURING CONSTRUCTION, THESE FACILITIES SHOULD BE PROTECTED FROM SILTATION DURING THE CONSTRUCTION PHASE.

SUGGESTED BMP'S/BMP'S TO BE USED

. FLOW RATES WILL CHANGE AS THE PURPOSE OF THIS PROJECT IS TO REROUTE SQUALICUM CREEK TO A NEW CHANNEL. RUNOFF FROM ALL NEW PERVIOUS AREAS HAVE BEEN INCLUDED WITH THE CAPACITY MODELING OF THE NEW CREEK CHANNEL.

#### ELEMENT 4 - INSTALL SEDIMENT CONTROLS

(A) THE DUFF LAYER, NATIVE TOPSOIL, AND NATURAL VEGETATION SHALL BE RETAINED IN AN UNDISTURBED STATE TO THE MAXIMUM EXTENT PRACTICABLE.

(B) PRIOR TO LEAVING A CONSTRUCTION SITE, OR PRIOR TO DISCHARGE TO AN INFILTRATION FACILITY, STORMWATER RUNOFF FROM DISTURBED AREAS SHALL PASS THROUGH A SEDIMENT POND OR OTHER APPROPRIATE SEDIMENT REMOVAL BMP, UP, TO, AND INCLUDING FLOCCULATION TREATMENT. RUNOFF FROM FULLY STABILIZED AREAS MAY BE DISCHARGED WITHOUT A SEDIMENT REMOVAL BMP, BUT MUST MEET THE FLOW CONTROL PERFORMANCE STANDARD OF FLEMENT 3 ABOVE, FULL STABILIZATION MEANS THE USE OF ROLLED FROSION PRODUCTS, A BONDED FIBER MATRIX PRODUCT, OR VEGETATIVE COVER IN A MANNER THAT WILL FULLY PREVENT SOIL EROSION. SEDIMENT PONDS, VEGETATED BUFFER STRIPS, SEDIMENT BARRIERS OR FILTERS, DIKES, AND OTHER BMPS INTENDED TO TRAP SEDIMENT ON-SITE SHALL BE CONSTRUCTED AS ONE OF THE FIRST STEPS IN GRADING, THESE BMPS SHALL BE FUNCTIONAL BEFORE OTHER LAND DISTURBING ACTIVITIES TAKE PLACE.

(C) EARTHEN STRUCTURES SUCH AS DAMS, DIKES, AND DIVERSIONS SHALL BE SEEDED AND MULCHED ACCORDING TO THE TIMING INDICATED IN ELEMENT 5 BELOW.

SUGGESTED BMP'S/BMP'S TO BE USED:

- . BMP C235: STRAW WATTLES
- . BMP T6.10: PRESETTLING BASIN



#### ELEMENT 5 - STABILIZE SOILS

(A) ALL EXPOSED AND UNWORKED SOILS SHALL BE STABILIZED BY APPLICATION OF EFFECTIVE BMPS THAT PROTECT THE SOIL FROM THE FROSIVE FORCES OF RAINDROP IMPACT AND FLOWING WATER AND WIND FROSION

(8) FROM OCTOBER 1 THROUGH APRIL 30 OF EACH YEAR, NO SOILS SHALL REMAIN EXPOSED AND UNWORKED FOR MORE THAN 2 DAYS. FROM MAY 1 TO SEPTEMBER 30 OF EACH YEAR, NO SOILS SHALL REMAIN EXPOSED AND UNWORKED FOR MORE THAN 7 DAYS. THIS CONDITION APPLIES TO ALL SOILS ON SITE, WHETHER AT FINAL GRADE OR NOT.

(C) APPLICABLE PRACTICES INCLUDE, BUT ARE NOT LIMITED TO, TEMPORARY AND PERMANENT SEEDING, SODDING, MULCHING, PLASTIC COVERING, SOIL APPLICATION OF POLYACRYLAMIDE (PAM), EARLY APPLICATION OF GRAVEL BASE ON AREAS TO BE PAVED, AND DUST CONTROL

(D) SOIL STABILIZATION MEASURES SELECTED SHOULD BE APPROPRIATE FOR THE TIME OF YEAR, SITE CONDITIONS, ESTIMATED DURATION OF USE. ÀND POTENTIAL WATER QUALITY IMPACTS THAT STABILIZATION AGENTS MAY HAVE ON DOWNSTREAM WATERS OR GROUND WATER.

(E) SOIL STOCKPILES MUST BE STABILIZED AND PROTECTED WITH SEDIMENT TRAPPING MEASURES.

(F) WORK ON LINEAR CONSTRUCTION SITES AND ACTIVITIES, INCLUDING RIGHT-OF-WAY AND EASEMENT CLEARING, SHALL NOT EXCEED THE CAPABILITY OF THE INDIVIDUAL CONTRACTOR FOR HIS PORTION OF THE PROJECT TO INSTALL THE AGGREGATE AND SOIL MATERIALS AND CREEK CHANNEL, AND TO RE-STABILIZE THE DISTURBED SOILS, MEETING THE TIMING CONDITIONS LISTED ABOVE.

(G) IN ADDITION, AT THE DISCRETION OF THE PUBLIC WORKS DIRECTOR THOSE SITES UNABLE TO MAINTAIN THE QUALITY OF THEIR STORMWATER DISCHARGE MAY BE REQUIRED TO PROVIDE SOIL STABILIZATION TO ALL EXPOSED SOIL AREAS REGARDLESS OF THE WORKING STATUS OF THE

(J) REVEGETATION WILL BE ACCOMPLISHED BY THE CITY FOLLOWING CONSTRUCTION. WASHINGTON CONSERVATION CORPS CREWS WILL PERFORM THE PLANTING. ALL SIDESLOPES OF THE NEW CREEK CHANNEL TO BE COVERED IN EROSION CONTROL MAT AS DETAILED IN THE PROJECT DRAWINGS, AND UPLANDS SEEDED AND MULCHED AS SHOWN.

#### SUGGESTED BMP'S/BMP'S TO BE USED:

- BMP C120: TEMPORARY AND PERMANENT SEEDING
- BMP C124: SODDING BMP C140: DUST CONTROL
- BMP T.5.13: POST-CONSTRUCTION SOIL QUALITY AND DEPTH

#### ELEMENT 6 - PROTECT SLOPES

(A) CUT AND FILL SLOPES SHALL BE DESIGNED AND CONSTRUCTED IN A MANNER THAT WILL MINIMIZE EROSION.

(B) CONSIDER SOIL TYPE AND ITS POTENTIAL FOR EROSION.

(c) REDUCE SLOPE RUNOFF VELOCITIES BY REDUCING THE CONTINUOUS LENGTH OF SLOPE WITH TERRACING AND DIVERSIONS, REDUCE SLOPE STEEPNESS, AND ROUGHEN SLOPE SURFACE.

(D) DIVERT UPSLOPE DRAINAGE AND RUN-ON WATERS FROM OFF-SITE WITH INTERCEPTORS AT TOP OF SLOPE. OFF-SITE STORMWATER SHOULD BE HANDLED SEPARATELY FROM STORMWATER GENERATED ON THE SITE. DIVERSION OF OFF-SITE STORMWATER AROUND THE SITE MAY BE A VIABLE OPTION, DIVERTED FLOWS SHALL BE REDIRECTED TO THE NATURAL DRAINAGE LOCATION AT OR BEFORE THE PROPERTY BOUNDARY.

(E) CONTAIN DOWN SLOPE COLLECTED FLOWS IN PIPES, SLOPE DRAINS, OR PROTECTED CHANNELS.

(F) PROVIDE DRAINAGE TO REMOVE GROUND WATER INTERSECTING THE SLOPE SURFACE OF EXPOSED SOIL AREAS.

(G) EXCAVATED MATERIAL SHALL BE PLACED ON THE UPHILL SIDE OF TRENCHES, CONSISTENT WITH SAFETY AND SPACE CONSIDERATIONS.

(H) CHECK DAMS SHALL BE PLACED AT REGULAR INTERVALS WITHIN TRENCHES THAT ARE CUT DOWN A SLOPE.

(I) STABILIZE SOILS ON SLOPES, AS SPECIFIED IN ELEMENT #5.

(J) REVEGETATION WILL BE ACCOMPLISHED BY THE CITY FOLLOWING CONSTRUCTION. WASHINGTON CONSERVATION CORPS CREWS WILL PERFORM THE PLANTING. ALL SIDESLOPES OF THE NEW CREEK CHANNEL TO BE COVERED IN EROSION CONTROL MAT AS DETAILED IN THE PROJECT DRAWINGS, AND UPLANDS SEEDED AND MULCHED AS SHOWN.

#### SUGGESTED BMP'S/BMP'S TO BE USED:

- BMP C123: PLASTIC COVERING BMP C130: SURFACE ROUGHENING
- **ELEMENT 7: PROTECT DRAIN INLETS**

(A) ALL STORM DRAIN INLETS MADE OPERABLE DURING CONSTRUCTION, AND NEAR CONSTRUCTION ENTRANCES SHALL BE PROTECTED SO THAT STORMWATER RUNOFF SHALL NOT ENTER THE CONVEYANCE SYSTEM WITHOUT FIRST BEING FILTERED OR TREATED TO REMOVE SEDIMENT.

(B) ALL APPROACH ROADS SHALL BE KEPT CLEAN, AND ALL SEDIMENT AND STREET WASH WATER SHALL NOT BE ALLOWED TO ENTER STORM DRAINS WITHOUT PRIOR AND ADEQUATE TREATMENT UNLESS TREATMENT IS PROVIDED BEFORE THE STORM DRAIN DISCHARGES TO WATERS OF

SUGGESTED BMP'S/BMP'S TO BE USED:

BMP C220: STORM DRAIN INLET PROTECTION

#### **ELEMENT 8: STABILIZE CHANNELS AND OUTLETS**

(A) ALL TEMPORARY ON-SITE CONVEYANCE CHANNELS SHALL BE DESIGNED, CONSTRUCTED AND STABILIZED TO PREVENT EROSION FROM THE EXPECTED VELOCITY OF FLOW FROM A 2 YEAR, 24-HOUR FREQUENCY STORM FOR THE DEVELOPED CONDITION

(B) STABILIZATION, INCLUDING ARMORING MATERIAL, ADEQUATE TO PREVENT EROSION OF OUTLETS. ADJACENT STREAM BANKS, SLOPES AND DOWNSTREAM REACHES SHALL BE PROVIDED AT THE OUTLETS OF ALL CONVEYANCE SYSTEMS

SUGGESTED BMP'S/BMP'S TO BE USED:

BMP C209: OUTLET PROTECTION

#### ELEMENT 9: CONTROL POLLUTANTS

(A) ALL POLLUTANTS, INCLUDING WASTE MATERIALS AND DEMOLITION DEBRIS, THAT OCCUR ON-SITE DURING CONSTRUCTION SHALL BE HANDLED AND DISPOSED OF IN A MANNER THAT DOES NOT CAUSE CONTAMINATION OF STORMWATER.

(B) COVER, CONTAINMENT, AND PROTECTION FROM VANDALISM SHALL BE PROVIDED FOR ALL CHEMICALS, LIQUID PRODUCTS, PETROLEUM PRODUCTS, AND NON-INERT WASTES PRESENT ON THE SITE (SEE CHAPTER 173-304 WAC, AS CURRENTLY ENACTED OR HEREAFTER MODIFIED. FOR THE DEFINITION OF INERT WASTE, WHICH IS INCORPORATED HEREIN BY THIS REFERENCE).

(C) MAINTENANCE AND REPAIR OF HEAVY EQUIPMENT AND VEHICLES INVOLVING OIL CHANGES, HYDRAULIC SYSTEM DRAIN DOWN, SOLVENT AND DE-GREASING CLEANING OPERATIONS, FUEL TANK DRAIN DOWN AND REMOVAL, AND OTHER ACTIVITIES WHICH MAY RESULT IN DISCHARGE OR SPILLAGE OF POLLUTANTS TO THE GROUND OR INTO STORMWATER RUNOFF MUST BE CONDUCTED USING SPILL PREVENTION MEASURES, SUCH AS DRIP PANS, CONTAMINATED SURFACES SHALL BE CLEANED IMMEDIATELY FOLLOWING ANY DISCHARGE OR SPILL INCIDENT, EMERGENCY REPAIRS MAY BE PERFORMED ON-SITE USING TEMPORARY PLASTIC PLACED BENEATH AND, IF RAINING, OVER THE VEHICLE.

(D) WHEEL WASH, OR TIRE BATH WASTEWATER, SHALL BE DISCHARGED TO A SEPARATE ON-SITE TREATMENT SYSTEM OR TO THE SANITARY

(E) APPLICATION OF AGRICULTURAL CHEMICALS, INCLUDING FERTILIZERS AND PESTICIDES, SHALL BE CONDUCTED IN A MANNER AND AT APPLICATION RATES THAT WILL NOT RESULT IN LOSS OF CHEMICAL TO STORMWATER RUNOFF. MANUFACTURERS' RECOMMENDATIONS SHALL BE FOLLOWED FOR APPLICATION RATES AND PROCEDURES.

(F) MANAGEMENT OF PH-MODIFYING SOURCES SHALL PREVENT CONTAMINATION OF RUNOFF AND STORMWATER COLLECTED ON THE SITE. THESE SOURCES INCLUDE, BUT ARE NOT LIMITED TO, BULK CEMENT, CEMENT KILN DUST, FLY ASH, NEW CONCRETE WASHING AND CURING WATERS, WASTE STREAMS GENERATED FROM CONCRETE GRINDING AND SAWING, EXPOSED AGGREGATE PROCESSES, AND CONCRETE PUMPING AND MIXER WASHOUT WATERS.

#### ELEMENT 10: CONTROL DE-WATERING

(A) ALL TRENCH DE-WATERING WATER, WHICH HAS SIMILAR CHARACTERISTICS TO STORMWATER RUNOFF AT THE SITE, SHALL BE DISCHARGED INTO A CONTROLLED CONVEYANCE SYSTEM, PRIOR TO DISCHARGE TO A SEDIMENT TRAP OR SEDIMENT POND. CHANNELS MUST BE STABILIZED,

(B) CLEAN NON-TURBID DE-WATERING WATER SUCH AS WELL-POINT GROUND WATER CAN BE DISCHARGED TO SYSTEMS TRIBUTARY TO STATE SURFACE WATERS, AS SPECIFIED IN ELEMENT #8, PROVIDED THE DE-WATERING FLOW DOES NOT CAUSE EROSION OR FLOODING OF THE RECEIVING WATERS. THESE CLEAN WATERS SHOULD NOT BE ROUTED THROUGH SEDIMENT PONDS WITH STORMWATER

(C) HIGHLY TURBID OR OTHERWISE CONTAMINATED DEWATERING WATER, SUCH AS FROM CONSTRUCTION EQUIPMENT OPERATION, CLAMSHELL DIGGING CONCRETE TREMIE POLIR OR WORK INSIDE A COFFERDAM SHALL BE HANDLED SEPARATELY FROM STORMWATER AT THE SITE

(D) OTHER DISPOSAL OPTIONS, DEPENDING ON SITE CONSTRAINTS, MAY INCLUDE, BY WAY OF EXAMPLE: 1) INFILTRATION, 2) TRANSPORT OFF-SITE IN VEHICLE, SUCH AS A VACUUM FLUSH TRUCK, FOR LEGAL DISPOSAL IN A MANNER THAT DOES NOT POLLUTE STATE WATERS. 3) ON-SITE TREATMENT USING CHEMICAL TREATMENT OR OTHER SUITABLE TREATMENT TECHNOLOGIES.

SUGCESTED BMP'S/BMP'S TO BE USED:

#### ELEMENT 11: MAINTAIN BMPS

(A) ALL TEMPORARY AND PERMANENT EROSION AND SEDIMENT CONTROL BMPS SHALL BE MAINTAINED AND REPAIRED AS NEEDED TO ASSURE CONTINUED PERFORMANCE OF THEIR INTENDED FUNCTION, ALL MAINTENANCE AND REPAIR SHALL BE CONDUCTED IN ACCORDANCE ₩ITH BMPS.

(B) SEDIMENT CONTROL BMPS SHALL BE INSPECTED WEEKLY OR AFTER A RUNOFF-PRODUCING STORM EVENT DURING THE DRY SEASON AND DAILY DURING THE WET SEASON, ALL PROJECTS THAT DISTURB AN AREA GREATER THAN ONE ACRE SHALL HAVE A CERTIFIED EROSION CONTROL LEAD AVAILABLE TO THE SITE. THIS EROSION CONTROL LEAD SHALL BE RESPONSIBLE TO PROVIDE OVERVIEW OF ONGOING DAY TO DAY EROSION CONTROL REQUIREMENTS. THE EROSION CONTROL LEAD SHALL (WITHIN 24 HOURS) REPORT TO THE CITY AND DEPARTMENT OF ECOLOGY ANY SITE DISCHARGES THAT EXCEED STATE WATER QUALITY STANDARDS THAT HAVE OR ARE LIKELY TO HAVE ENTERED WATERS OF THE STATE.

(C) ALL TEMPORARY EROSION AND SEDIMENT CONTROL BMPS SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION IS ACHIEVED. OR AFTER THE TEMPORARY BMPS ARE NO LONGER NEEDED. TRAPPED SEDIMENT SHALL BE REMOVED OR STABILIZED ON SITE. DISTURBED SOIL AREAS RESULTING FROM REMOVAL OF BMPS OR VEGETATION SHALL BE PERMANENTLY STABILIZED.

#### ELEMENT 12: MANAGE THE PROJECT

(A) PHASING OF CONSTRUCTION - DEVELOPMENT PROJECTS SHALL BE PHASED WHERE FEASIBLE IN ORDER TO PREVENT, TO THE MAXIMUM EXTENT PRACTICABLE, THE TRANSPORT OF SEDIMENT FROM THE DEVELOPMENT SITE DURING CONSTRUCTION, REVEGETATION OF EXPOSED AREAS AND MAINTENANCE OF THAT VEGETATION SHALL BE AN INTEGRAL PART OF THE CLEARING ACTIVITIES FOR ANY PHASE.

(B) WHEN ESTABLISHING THESE PERMITTED CLEARING AND GRADING AREAS, CONSIDERATION SHOULD BE GIVEN TO MINIMIZING REMOVAL OF EXISTING TREES AND MINIMIZING DISTURBANCE/COMPACTION OF NATIVE SOILS EXCEPT AS NEEDED FOR BUILDING PURPOSES. PERMITTED CLEARING AND GRADING AREAS AND ANY OTHER AREAS REQUIRED TO PRESERVE CRITICAL OR SENSITIVE AREAS, BUFFERS, NATIVE GROWTH PROTECTION EASEMENTS, OR TREE RETENTION AREAS, SHALL BE DELINEATED ON THE SITE PLANS AND THE DEVELOPMENT SITE.

(C) COORDINATION WITH UTILITIES AND OTHER CONTRACTORS - THE PRIMARY PROJECT PROPONENT SHALL EVALUATE, WITH INPUT FROM UTILITIES AND OTHER CONTRACTORS, THE STORMWATER MANAGEMENT REQUIREMENTS FOR THE ENTIRE PROJECT, INCLUDING THE UTILITIES, WHEN PREPARING THE CONSTRUCTION SWPPP.

(D) INSPECTION AND MONITORING - ALL BMPS SHALL BE INSPECTED, MAINTAINED, AND REPAIRED AS NEEDED TO ASSURE CONTINUED PERFORMANCE OF THEIR INTENDED FUNCTION.

(E) FOR ANY PROJECT DISTURBING MORE THAN ONE ACRE, A CERTIFIED PROFESSIONAL IN EROSION AND SEDIMENT CONTROL SHALL BE IDENTIFIED IN THE CONSTRUCTION SWPPP AND SHALL BE ON-SITE OR ON-CALL AT ALL TIMES, CERTIFICATION MAY BE THROUGH THE WASHINGTON STATE DEPARTMENT OF TRANSPORTATION/ASSOCIATED GENERAL CONTRACTORS (WSDOT/AGC) CONSTRUCTION SITE EROSION AND SEDIMENT CONTROL CERTIFICATION PROGRAM OR ANY EQUIVALENT LOCAL OR NATIONAL CERTIFICATION AND/OR TRAINING PROGRAM, IN THE CITY'S

(F) WHENEVER INSPECTION AND/OR MONITORING REVEALS THAT THE BMPS IDENTIFIED IN THE CONSTRUCTION SWPPP ARE INADEQUATE, DUE TO HE ACTUAL DISCHARGE OF OR POTENTIAL TO DISCHARGE A SIGNIFICANT AMOUNT OF ANY POLLUTANT, THE SWPPP SHALL BE MODIFIED, AS

(G) MAINTENANCE OF THE CONSTRUCTION SWPPP - THE CONSTRUCTION SWPPP SHALL BE RETAINED ON-SITE. THE CONSTRUCTION SWPPP SHALL BE MODIFIED WHENEVER THERE IS A SIGNIFICANT CHANGE IN THE DESIGN, CONSTRUCTION, OPERATION, OR MAINTENANCE OF ANY BMP.



11	14		
	3		
	2		
Ţ.	11		
Date	No	Revision	Ву
CONTACT PERSON:		ENGINEER	, Р

DIR. PUBLIC WORKS\_ TC RAR CITY ENGINEER\_ OPER, ENGINEER.

CITY OF BELLINGHAM, WASHINGTON PUBLIC WORKS DEPARTMENT ENGINEERING DIVISION

DATUM NADR3/91 NAVD88

SCALE


Horiz

Vert.

Job. No. Date 04/30/15 Field Bk .\_

SQUALICUM CREEK RE-ROUTE HABITAT ENHANCEMENT PROJECT CONSTRUCTION STORMWATER POLLUTION PREVENTION PLAN (SWPPP)

SEE CONSTRUCTION SEQUENCE SHEETS 7-8 AND SHEETS 2-34 FOR APPROXIMATE LOCATIONS OF SEDIMENT AND WATER CONTROLS.



## TEMPORARY COFFERDAM

(WATER DEPTH LESS THAN 2.5') NO SCALE

## **BULK BAG GENERAL NOTES:**

BULK BAG COFFERDAM SHALL BE CONSTRUCTED OF SEVERAL UNITS OF BULK BAGS FILLED WITH "STREAMBED SEDIMENT" (SEE TABLE), AND ABUTTED SIDE BY SIDE TO CREATE A ROW THAT ISOLATES THE CONSTRUCTION SITE FROM THE WATERWAY. IF WATER DEPTH EXCEEDS 85% OF THE BULK BAG HEIGHT, AN ADDITIONAL TOP ROW OF BULK BAGS SHALL BE INSTALLED, SUPPORTED BY TWO BOTTOM ROWS OF BULK BAGS. BULK BAG COFFERDAM SHALL BE SEALED BY COVERING THE COFFERDAM WITH PLASTIC SHEETING HELD IN PLACE BY STANDARD SANDBAGS PLACED IN ROWS ON TOP OF COFFERDAM, AND AT TOE OF COFFERDAM. THE PLASTIC SHEETING SHALL BE DRAPED ALONG THE CHANNEL BOTTOM ON THE WORK AREA SIDE OF THE COFFERDAM WITH OUTWARD EDGE OF SHEETING MINIMUM 3-FEET FROM TOE OF COFFERDAM. THE DRAPED PORTION OF PLASTIC SHEETING SHALL BE PINNED TO THE CHANNEL BED BY MINIMUM TWO ROWS OF STANDARD SANDBAGS. THE OUTWARD EDGE OF PLASTIC SHEETING SHALL BE KEYED INTO THE CHANNEL BED MINIMUM 1-FT. KEYING IN THE OUTWARD EDGE OF PLASTIC SHEETING SHALL OCCUR AFTER THE COFFERDAM IS CLOSED TO PREVENT TURBIDITY RELEASE TO THE WATERWAY.

IF POSSIBLE, THE COFFERDAM SHALL BE EXTENDED ONTO A GRAVEL BAR AND OUT OF THE WATER. IF THE END MUST BE TERMINATED AT THE RIVERBANK, THE COFFERDAM SHALL BE TIGHTLY SEALED TO THE GROUND BY PLASTIC SHEETING AND STANDARD SANDBAGS. MULTIPLE LAYERS OF SHEETING AND SANDBAGS MAY BE REQUIRED TO FORM A WATERTIGHT SEAL.


BULK BAGS SHALL BE WATERPROOF CUBE-SHAPED POLYPROPYLENE WOVEN FABRIC BAGS WITH FULLY OPEN TOP, FLAT BOTTOM, FOUR LOOPS, MINIMUM 2-TON WEIGHT CAPACITY, MINIMUM 5:1 SAFETY FACTOR.


PLASTIC SHEETING SHALL BE MINIMUM 6-MIL THICKNESS. PLASTIC SHEETING SHALL COVER THE ENTIRE LENGTH OF COFFERDAM WITHOUT SEAMS.

BULK BAG COFFERDAM SHALL BE COMPLETELY REMOVED AFTER CONSTRUCTION IS COMPLETED AND TURBIDITY HAS BEEN REMOVED.

ALTERNATE COFFERDAM MATERIALS AND CONFIGURATIONS MAY BE ALLOWED BUT SHALL NOT BE IMPLEMENTED WITHOUT REVIEW AND APPROVAL BY THE OWNER. CONTRACTOR SHALL PROVIDE SHOP DRAWINGS AND/OR VENDOR CUT SHEETS FOR SUBSTITUTIONS.










Figure 4.1.2 - Wheel Wash

STREAM CROSSINGS FOR ACCESS:


INSTALL CULVERTS IN TRIBUTARY W WHERE ACCESS ROUTES CROSS THE CREEK.

ACCESS FROM IRONGATE RD. AND FROM JAMES ST WILL EACH REQUIRE A CULVERT.

EACH CULVERT SHALL CONVEY 24 CFS (10% CHANCE OF OCCURRENCE).

FILL PLACED OVER THE CULVERT TO PROVIDE ACCESS ROAD SHALL BE GRANULAR MATERIAL.

REMOVE CULVERTS AND FILL MATERIAL AS SOON AS THEY ARE NO LONGER NEEDED FOR HEAVY EQUIPMENT ACCESS OR EGRESS.



PROJECT ENGINEER MRM DIR. PUBLIC WORKS\_ TC MRM DESIGNED/DRAWN \_ CITY ENGINEER\_ OPER, ENGINEER.

CITY OF BELLINGHAM. WASHINGTON PUBLIC WORKS DEPARTMENT **ENGINEERING DIVISION** 

Pay ( Houth

SCALE Horiz. Vert.

DATUM Job. No. Date 04/30/15 NAD83/91 NAVD88 Field Bk.\_

SQUALICUM CREEK RE-ROUTE HABITAT ENHANCEMENT PROJECT SWPPP DETAILS

NEW JAMES STREET BRIDGE CONSTRUCTED 2014 380317-196099 380318-245113 380318-490113 "COLD STORAGE" TRIB W 380317-196099 TRIB W EXISTING WETLAND TRIB V MITIGATION SITE 380318-386082 ( E. ... "ALLSOP" 380318-532082 380318-477082 BUG LAKE -SUNSET POND 380318-78052 EXISTING SQUALICUM CREEK 380318-366016 380315-524006 EXISTING SQUALICUM CREEK

EXISTING STREAMS
THE EXISTING SQUALICUM CREEK
BEGINS AT THE NORTHEAST CORNER OF SUNSET POND, FLOWING THROUGH THE POND, EXITING THE POND AT THE SOUTHWEST CORNER, CONTINUING THROUGH A CULVERT UNDER JAMES STREET AND WESTWARD IN A DITCHED CHANNEL TO TWIN CULVERTS UNDER INTERSTATE 5. IT CONTINUES NORTHWEST TO THE SOUTH SIDE OF BUG LAKE.

TRIB W FLOWS IN A DITCH ALONG THE NORTH SIDE OF THE OLD RAILROAD.

TRIB V IS A STORMWATER DITCH ALONG THE SOUTH SIDE OF THE


WETLANDS AND WETLAND MITIGATION AREAS ARE WITHIN AND ADJACENT TO THE PROJECT SITE.

A NEW BRIDGE HAS BEEN CONSTRUCTED AT THE JAMES STREET CROSSING OF TRIBUTARIES W AND V. SCOUR PROTECTION STONE HAS BEEN INSTALLED UNDER THE BRIDGE ALONG THE FOOTINGS AND ACROSS THE CHANNELS.

STORMWATER RUNOFF EXISTING STORMWATER RUNOFF GENERALLY FLOWS WESTWARD, OR TOWARD DITCHES ADJACENT TO THE RAILROAD. RUNOFF FROM DEVELOPED AREAS FLOWS TOWARD CATCH BASINS AND DITCHES THAT CONVEY FLOW AWAY FROM THE RE-ROUTE

EXISTING VEGETATION VEGETATION IS RIPARIAN FOREST COTTONWOOD AND ALDER TREES. WITH THICK UNDERSTORY SHRUBS PREDOMINANTLY ROSE, DOGWOOD, AND SNOWBERRY, MIXED WITH HIMALAYAN BLACKBERRY.

**PLAN VIEW EXISTING CONDITIONS** 





CONTACT PERSON:

MRM PROJECT ENGINEER DESIGNED/DRAWN \_ MRM INSPECTOR \_

DIR. PUBLIC WORKS TC CITY ENGINEER\_\_ OPER. ENGINEER\_

CITY OF BELLINGHAM. WASHINGTON PUBLIC WORKS DEPARTMENT ENGINEERING DIVISION

SCALE


Horiz.

Vert.

DATUM Job. No. NAD83/91 NAVD88

Date 04/30/15 Field Bk.\_

SQUALICUM CREEK RE-ROUTE HABITAT ENHANCEMENT PROJECT EXISTING CONDITIONS





CONTACT PERSON:

CITY OF BELLINGHAM, WASHINGTON
PUBLIC WORKS DEPARTMENT
ENGINEERING DIVISION


SCALE
Horiz. \_\_\_\_\_
Vert. \_\_\_\_

DATUM NAD83/91 NAVD88

SQUALICUM CREEK RE-ROUTE HABITAT ENHANCEMENT PROJECT PROJECT OVERVIEW

SHEET 6

EXPIRES 09-25-2016



- $\left(\,2\,
  ight)$  install 20 wattles in trib W, one every 100'.
- INSTALL FISH SCREEN AND TEMPORARY COFFERDAM #1 WHERE RE-ROUTE CHANNEL OUTLETS TO BUG LAKE. DEFISH IMPOUNDED AREA. CONSTRUCT A SUMP AND INSTALL PUMP. PUMP WILL COLLECT SEDIMENT LADEN WATER DEVELOPED DURING CONSTRUCTION AND PUMP TO INFILTRATION AREA. INSTALL BMP'S AS NEEDED TO PREVENT TURBIDITY FROM ENTERING BUG LAKE.
- 4 ) CLEAR AND GRUB I-5 TO BUG LAKE.
- CONSTRUCT CHANNEL FROM BUG LAKE TO I-5. APPLY FILL TO DESIGNATED TRIB V AREA. EXCESS FILL TO BE DISPOSED OF OFF SITE.
- REMOVE PUMP AND COFFERDAM #1. FISH SCREEN REMAINS.
- INSTALL FISH SCREENS IN TRIB W; ONE AT CONFLUENCE WITH SQUALICUM CREEK (7a), ONE 400' UPSTREAM OF JAMES STREET (7b). THE OWNER, WITH CONTRACTOR COORDINATION AND ASSISTANCE, WILL RESCUE FISH IN THIS TRIB W EXCLUSION AREA.
- INSTALL TEMPORARY COFFERDAM #2 IN UPSTREAM END OF I-5 CULVERT. CONSTRUCT A SUMP IN THE CHANNEL AND INSTALL PUMP. PUMP WILL COLLECT SEDIMENT LADEN WATER DEVELOPED DURING CONSTRUCTION. PUMP TO TRIB W.
- CONTINUE CONSTRUCTION OF CHANNEL FROM I-5 TO APPROXIMATELY HALF WAY TO JAMES ST. APPLY FILL TO DESIGNATED TRIB V AREAS.

- INSTALL COFFERDAM #3 IN TRIB W. PUMP TO DIVERT CLEAN WATER TO SUNSET POND.
- CONTINUE CHANNEL CONSTRUCTION TO JAMES STREET. CONSTRUCT CHANNEL UNDER JAMES ST. CONNECT TRIB W TO RE-ROUTE CHANNEL. APPLY FILL TO DESIGNATED TRIB W AREA. EXCESS FILL TO BE HAULED OFF SITE. DO NOT REMOVE EXSISTING SCOUR PROTECTION STONE (12) UNDER JAMES STREET BRIDGE.
- $\left(13
  ight)$  remove cofferdam #2 and pump. remove cofferdam #3 and pump. Trib w will flow into New Re-route Ch/
- INSTALL BERMS AND FLOOD CULVERTS.

Vert.

INSTALL COFFERDAM #4 AND PUMP CONSTRUCTION WATER TO INFILTRATION AREAS. (CONTINUED ON PHASE 2 SEQUENCE)
NOTES:

SQUALICUM CREEK WILL FLOW IN ITS EXISTING CHANNEL FOR THE ENTIRETY OF PHASE I CONSTRUCTION.

GROUNDWATER WILL BE ENCOUNTERED. PUMPING WILL BE REQUIRED TO REMOVE CONSTRUCTION WATER FROM THE WORK AREA AND DISCHARGE IT TO INFILTRATION AREAS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO ENSURE THAT NO TURBIDITY ENTERS THE WATERWAY. ADDITIONAL CONTROLS MAY BE REQUIRED AT THE CONTRACTOR'S EXPENSE.




PROJECT ENGINEER DIR. PUBLIC WORKS\_ DESIGNED/DRAWN CITY ENGINEER\_ INSPECTOR OPER. ENGINEER. Revision

CITY OF BELLINGHAM, WASHINGTON PUBLIC WORKS DEPARTMENT **ENGINEERING DIVISION** 

DATUM SCALE NAD83/91 Horiz. NAVD88

Job. No. Date 04/30/15 Field Bk..



- 14) FROM PHASE 1 SEQUENCE INSTALL COFFERDAM #4. CONSTRUCT A SUMP AND INSTALL PUMP. PUMP CONSTRUCTION WATER TO INFILTRATION AREAS DURING CONTINUED UPSTREAM CHANNEL CONSTRUCTION.
- (15) install cofferdam #5 at sunset pond connection.
- (16) construct channel up to pond connection.
- (17) REMOVE COFFERDAM #4 AND PUMP. REMOVE COFFERDAM #5.
- (18) install cofferdam #6 and pump. Pump construction water to infiltration area.
- CONTINUE UPSTREAM CHANNEL CONSTRUCTION WHILE SQUALICUM CREEK FLOWS TO SUNSET POND IN ITS EXISTING ALIGNMENT. LEAVE 20 FEET OF GROUND AS A TEMPORARY BERM BETWEEN UPSTREAM END NEW CHANNEL AND EXISTING CREEK. APPLY FILL TO DESIGNATED TRIB V AREA. EXCESS FILL TO BE HAULED OFF SITE.
- (20) INSTALL FISH SCREEN IN SQUALICUM CREEK AND SUNSET POND. RESCUE FISH FROM THE EXCLUSION AREA.
- (21) install cofferdam (#7) to divert squalicum creek to trib v (concurrent with next step).
- (22) INSTALL COFFERDAM (#8) TO DIVERT TRIB V THROUGH EXISTING CULVERT TO TRIB W.

- CONNECT NEW CHANNEL TO SQUALICUM CREEK BY REMOVING TEMPORARY BERM (STEP 19) AND CONTINUING UPSTREAM CHANNEL CONSTRUCTION.

  INSTALL COFFERDAM #9 AND FILL EXISTING CREEK BETWEEN UPSTREAM END OF NEW CHANNEL AND SUNSET POND. PUMP RESIDUAL WATER TO INFILTRATION AREA.
- (24) REMOVE COFFERDAM #6 AND PUMP.
- PERFORM FLOW RAMPING BY GRADUALLY REMOVING DIVERSION DAMS TO TRIB V AND TRIB W (#7 AND #8). REMOVE FISH SCREENS.
- 26) FILL REMAINDER OF TRIBUTARY V.
- 27) INSTALL COFFERDAM #10 AT SUNSET POND OUTLET CHANNEL. PUMP RESIDUAL WATER. RESCUE FISH IN EXISTING CHANNEL BETWEEN SUNSET POND AND BUG LAKE. FILL EXISTING CHANNEL BETWEEN SUNSET POND AND JAMES STREET. REMOVE COFFERDAM #10. REMOVE ALL FISH SCREENS.
- (28) IINSTALL STREAMBED SEDIMENT IN TRIB W AT DESIGNATED AREAS WEST OF 1-5 (SEE PHASE 1 SEQUENCE SHEET).

NOTES:
SQUALICUM CREEK WILL FLOW IN ITS EXISTING CHANNEL DURING PHASE II CONSTRUCTION UNTIL THE FINAL CONNECTION AND PERMANENT DIVERSION TO THE NEW CHANNEL.



CITY OF BELLINGHAM, WASHINGTON
PUBLIC WORKS DEPARTMENT
ENGINEERING DIVISION

 SCALE
 DATUM

 Horiz.
 NAD83/91

 Vert.
 NAVD88


SQUALICUM CREEK RE-ROUTE HABITAT ENHANCEMENT PROJECT
CONSTRUCTION SEQUENCE II
JAMES STREET TO SUNSET POND


8 0 8 4


EXPIRES 08-25-2016


Date No Revision By NSPECTOR —

CONTACT PERSON: ENGINEER . PROJECT ENGINEER AT 778—7900









OPER. ENGINEER\_

CAUTION! EXISTING GROUND CONTOUR OVERHEAD AND UNDERGROUND JTILITIES ARE KNOWN TO DESIGN GROUND CONTOUR EXIST IN AREA. NOT ALL ARE SHOWN IN PLANS. CLEARING LIMITS CALL UULC BEFORE YOU DIG. 2 BUSINESS DAYS ADVANCE NOTICE. COIR BLANKET (800) 424-5555

> POOL PLAN SCALE

STREAMBED SEDIMENT


PROTECT EXISTING SCOUR PROTECTION STONE

STAGING/STOCKPILE FILL AREA

ACCESS

Vert.


- 1. PROTECT SCOUR PROTECTION STONE THAT HAS BEEN INSTALLED UNDER/NEAR JAMES STREET BRIDGE. SEE SCOUR PROTECTION PLANS IN THE "RELATED INFORMATION" APPENDIX FOR DETAILS AND ADDITIONAL INFORMATION.
- 2. ALL ALCOVES, OXBOWS, AND SIDE CHANNELS (BLIND CHANNELS) SHALL BE GRADED TO DRAIN TOWARD THE CREEK.
- APPLY TRANSITION ZONE SEEDING TO STREAMBANKS BEFORE INSTALLING EROSION CONTROL BLANKET.
- APPLY 8' WIDE EROSION CONTROL BLANKET TO CONSTRUCTED STREAM BANKS (NOT REQUIRED AT LOG STRUCTURE AREAS).
- APPLY WOOD MULCH 4" DEEP TO CONSTRUCTED SURFACES THAT ARE LANDWARD OF EROSION CONTROL BLANKET.
- AFTER FINAL USE OF ACCESS ROUTES AND STOCKPILE AREAS, SCARIFY TO DECOMPACT TOPSOIL IF TOPSOIL HAS BEEN REMOVED TO FACILITATE ACCESS, AMEND TOPSOIL PER BMP T5.13. DO NOT SCARIFY "ACCESS ROAD".




SQUALICUM CREEK RE-ROUTE HABITAT ENHANCEMENT PROJECT Job. No. Date 04/30/15 PHASE I GRADING PLAN NAVD88 I-5 TO JAMES STREET Field Bk.\_


SHEET


INSPECTOR Date No Revision CONTACT PERSON: **ENGINEER** PROJECT ENGINEER AT 778-7900





Revision CONTACT PERSON: ENGINEER PROJECT ENGINEER AT 778-7900


















 Date
 No
 Revision
 By
 INSPECTOR
 —


 CONTACT PERSON:
 ENGINEER
 . PROJECT ENGINEER AT 778-7900












- EXISTING GROUND

### NOTES:

- 1. APPLY WOOD MULCH, 4" DEEP, TO CONSTRUCTED
- SURFACES (1,380 SY).

  2. AFTER FINAL USE OF ACCESS ROADS AND STOCKPILE AREAS, SCARIFY TO DECOMPACT TOPSOIL. IF TOPSOIL HAS BEEN REMOVED TO FACILITATE ACCESS, AMEND TOPSOIL PER BMP T5.13.





Revision

ENGINEER

CONTACT PERSON:

PROJECT ENGINEER DESIGNED/DRAWN . MRM INSPECTOR .

PROJECT ENGINEER AT 778-7900

DIR. PUBLIC WORKS TC CITY ENGINEER\_ OPER. ENGINEER\_

CITY OF BELLINGHAM, WASHINGTON PUBLIC WORKS DEPARTMENT ENGINEERING DIVISION


SCALE DATUM NAD83/91 NAVD88


Horiz.

Vert.


Job. No. Date 04/30/15 Field Bk.\_


SQUALICUM CREEK RE-ROUTE HABITAT ENHANCEMENT PROJECT SIDE CHANNEL 3





CONTACT PERSON: ENGINEER PROJECT ENGINEER AT 778-7900







AT THREE LOCATIONS ALONG TRIB W, STREAMBED SEDIMENT SHALL BE PLACED IN EXISTING SCOUR POOLS TO REDUCE FISH STRANDING HAZARD.

FILL POOLS TO BE LEVEL WITH ADJACENT STREAMBED LEVEL.

## STREAMBED SEDIMENT

STREAMBED SEDIMENT SHALL BE IMPORTED ROUNDED GRAVEL HAVING THE APPROXIMATE GRADATION OF WASHDOT STREAMBED SEDIMENT AS SPECIFIED IN SECTION 9-03.11(1) OF THE STANDARD SPECIFICATIONS, AND SUMMARIZED IN THE FOLLOWING TABLE:

Sieve Size	Percent Passing
21/2"	99-100
2"	65-95
1"	50-85
No. 4	26-44
No. 40	16 max.
No. 200	5.0-9.0

All percentages are by weight.


PIT RUN HAVING SIMILAR CHARACTERISTICS MAY BE ACCEPTABLE, AS DETERMINED BY THE ENGINEER.

### <u>LEGEND</u>



STREAMBED SEDIMENT





	4		
	3		
	2		
	1		
Date	Nο	Revision	By


CITY OF BELLINGHAM, WASHINGTON PUBLIC WORKS DEPARTMENT ENGINEERING DIVISION


SCALE Horiz. Vert.

DATUM NAD83/91 NAVD88

Job. No. Date 04/30/15 Field Bk.\_

SQUALICUM CREEK RE-ROUTE HABITAT ENHANCEMENT PROJECT FILL TRIB W SCOUR POOLS





CONTACT PERSON: Craig Mueller P.E., PROJECT ENGINEER AT 778-7900

PUBLIC WORKS DEPARTMENT ENGINEERING DIVISION

CITY OF BELLINGHAM, WASHINGTON

TAC

DIR. PUBLIC WORKS\_

CITY ENGINEER.

OPER. ENGINEER\_

SCALE Horiz. 1"=100' Vert.

Job. No. 2013-0122 Date 04/30/15 NAD 83/98 NAVD 88 Field Bk.\_

SQUALICUM CREEK RE-ROUTE HABITAT ENHANCEMENT PROJECT JAMES STREET TO IRONGATE HORIZONTAL CONTROL PLAN 1

SHEET 44

PROJECT ENGINEER

DESIGNED/DRAWN

INSPECTOR .

Vert.

NAVD 88

INSPECTOR CONTACT PERSON: Craig Mueller P.E., PROJECT ENGINEER AT 778-7900


DESIGNED/DRAWN

CITY ENGINEER.

OPER. ENGINEER\_

JAMES STREET TO IRONGATE HORIZONTAL CONTROL PLAN 2

44



Vert.


NAVD 88

CONTACT PERSON: Craig Mueller P.E., PROJECT ENGINEER AT 778-7900

INSPECTOR

OPER. ENGINEER\_

INTERIM BERM SITE PREP AND EROSION CONTROL PLAN 1



NAVD 88

Vert.

CONTACT PERSON: Craig Mueller P.E., PROJECT ENGINEER AT 778-7900


INSPECTOR

OPER. ENGINEER\_

12525 (Squalicum Creek Corridor)\CADD\Design\BERM\SCC-SPP-BERN.dwg \ xSCC\_RW\_BERM \ xSCC\_SP\_BERM \ LEIMKUHL \ xSCC\_EC\_BERM \ xS

2015 ame:

INTERIM BERM SITE PREP AND EROSION CONTROL PLAN 2




INSPECTOR CONTACT PERSON: Craig Mueller P.E., PROJECT ENGINEER AT 778-7900

2015 ame:

INTERIM BERM SITE PREP AND EROSION CONTROL PLAN 3


May Xref



#### MAINTENANCE STANDARDS

- 1. ANY DAMAGE SHALL BE REPAIRED IMMEDIATELY.
- 2. IF CONCENTRATED FLOWS ARE EVIDENT UPHILL OF THE FENCE, THEY MUST BE INTERCEPTED AND CONVEYED TO A SEDIMENT TRAP OR POND.
- 3. IT IS IMPORTANT TO CHECK THE UPHILL SIDE OF THE FENCE FOR SIGNS OF THE FENCE CLOGGING AND ACTING AS A BARRIER TO FLOW AND THEN CAUSING CHANNELIZATION OF FLOWS PARALLEL TO THE FENCE. IF THIS OCCURS, REPLACE THE FENCE OR REMOVE THE TRAPPED SEDIMENT.
- 4. SEDIMENT MUST BE REMOVED WHEN THE SEDIMENT IS 6" HIGH.
- 5. IF THE FILTER FABRIC HAS DETERIORATED DUE TO ULTRAVIOLET BREAKDOWN, IT SHALL BE REPLACED.






## NOTES:

REGULAR INSPECTION IS REQUIRED. SEDIMENT SHALL BE REMOVED AND FILTER MATERIAL REPLACED AS NEEDED.

INSPECTOR .







CITY OF BELLINGHAM, WASHINGTON PUBLIC WORKS DEPARTMENT ENGINEERING DIVISION


SCALE Horiz. NTS Vert.

Job. No. 2013-0122 Date 04/30/15 Field Bk.\_

SQUALICUM CREEK RE-ROUTE HABITAT ENHANCEMENT PROJECT JAMES STREET TO IRONGATE INTERIM BERM DETAILS









WATTLE

PROJECT ENGINEER \_ DESIGNED/DRAWN


TAC DIR. PUBLIC WORKS\_\_ OPER. ENGINEER\_


CITY ENGINEER\_

NAD 83/98 NAVD 88









DIR. PUBLIC WORKS\_\_ CITY ENGINEER\_

-EXIST GRADE

EXIST GRADE

-EXIST GRADE


PUBLIC WORKS DEPARTMENT **ENGINEERING DIVISION** 

Horiz. NTS Vert. NA

NAD 83/98 NAVD 88


SQUALICUM CREEK RE-ROUTE HABITAT ENHANCEMENT PROJECT JAMES STREET TO IRONGATE INTERIM BERM TYPICAL SECTIONS





# EQUALIZER CULVERTS CROSSING

# NTS STA 116+12 TO STA 117+29



# NOTES:

STRIPPING SHALL BE 24" DEEP FROM EXISTING GRADE AT WETLANDS, 15" AT EXISTING RAILROAD BERM, AND 15" AT ALL OTHER AREAS.

## **CONSTRUCTION NOTES:**

- 10 TOPSOIL TYPE B
- (11) STRIPPING INCL. HAUL, SEE NOTE 1
- (12) COMMON BORROW-MODIFIED, FLOOD BERM, INCL. HAUL
- (13) SEEDING, FERTILIZING, AND MULCHING
- 14 BIODEGRADABLE EROSION CONTROL BLANKET
- (15) CRUSHED SURFACING BASE COURSE
- (16) GRAVEL BORROW, INCL. HAUL
- 17 NOT USED
- (18) ROADWAY EXCAVATION INCL. HAUL





CITY OF BELLINGHAM, WASHINGTON

Job. No. <u>2013-0122</u> Date <u>04/30/15</u>

OPER. ENGINEER\_ CONTACT PERSON: Craig Mueller P.E., PROJECT ENGINEER AT 778-7900

**BIRCHWOOD BERM** NTS STA 211+33 TO STA 211+52

PROFILE GRADE
AND PIVOT POINT

PROFILE GRADE AND PIVOT POINT

<del>--(13)</del>

\<u>4</u>"(10)

PROFILE GRADE AND PIVOT POINT


6.0'

BIRCHWOOD BERM

STA 201+49 TO STA 211+00 STA 212+20 TO STA 212+49

**BIRCHWOOD BERM** 

STA 211+00 TO STA 211+33 STA 211+52 TO STA 212+20



PUBLIC WORKS DEPARTMENT

**ENGINEERING DIVISION** 

NAD 83/98

NAVD 88

Field Bk.\_

Vert. \_\_1"=10'

CONTACT PERSON: Craig Mueller P.E., PROJECT ENGINEER AT 778-7900

May Xref


DESIGNED/DRAWN

INSPECTOR

CITY ENGINEER\_

OPER. ENGINEER\_

JAMES STREET TO IRONGATE INTERIM BERM PLAN AND PROFILE 1 44



Vert. \_\_1"=10'

NAVD 88

Field Bk.\_

CONTACT PERSON: Craig Mueller P.E., PROJECT ENGINEER AT 778-7900

INSPECTOR

OPER. ENGINEER\_

INTERIM BERM PLAN AND PROFILE 2


44

## CONSTRUCTION NOTES:

- 4 CONSTRUCTION GEOTEXTILE FOR PERMANENT

## GENERAL NOTES:


- 1. FOR INTERIM BERM TYPICAL SECTIONS, SEE SHEET 36.
- 2. FOR CENTERLINE ALIGNMENT DATA, SEE SHEET 30.
- 3. CONTRACTOR TO LOCATE, POTHOLE, AND VERIFY DEPTHS OF EXISTING UTILITIES PRIOR TO EXCAVATION. DO NOT REMOVE. IF IN CONFLICT CONTACT GAS COMPANY. PROTECT IN PLACE.



EXIST WETLAND EXIST TREES

CRUSHED SURFACING BASE


QUARRY SPALLS



DIR. PUBLIC WORKS\_

CITY ENGINEER.

OPER. ENGINEER\_





Know what's below.

Call before you dig. Determina lo que esta bajo tierra. Llama antes de excavar.



2015 ame:

PROJECT ENGINEER \_ DESIGNED/DRAWN INSPECTOR


TAC

CITY OF BELLINGHAM, WASHINGTON PUBLIC WORKS DEPARTMENT ENGINEERING DIVISION

SCALE Horiz. \_\_1"=20' Vert. \_\_1"=10'

Job. No. 2013-0122 Date 04/30/15 NAD 83/98 NAVD 88

SQUALICUM CREEK RE-ROUTE HABITAT ENHANCEMENT PROJECT JAMES STREET TO IRONGATE INTERIM BERM PLAN AND PROFILE 3



Vert. \_\_1"=10'

NAVD 88

Field Bk.\_


CONTACT PERSON: Craig Mueller P.E., PROJECT ENGINEER AT 778-7900

INSPECTOR .

CITY ENGINEER\_

OPER. ENGINEER\_

JAMES STREET TO IRONGATE INTERIM BERM PLAN AND PROFILE 4



CITY OF BELLINGHAM, WASHINGTON

PUBLIC WORKS DEPARTMENT

**ENGINEERING DIVISION** 

TAC

DIR. PUBLIC WORKS\_

CITY ENGINEER.

OPER. ENGINEER\_

SQUALICUM CREEK RE-ROUTE HABITAT ENHANCEMENT PROJECT JAMES STREET TO IRONGATE INTERIM BERM PLAN AND PROFILE 5

Job. No. 2013-0122

Date 04/30/15

Field Bk.\_

NAD 83/98

NAVD 88

Horiz. \_\_1"=20'

Vert. \_\_1"=10'

SHEET 44


CONTACT PERSON: Craig Mueller P.E., PROJECT ENGINEER AT 778-7900

PROJECT ENGINEER \_

DESIGNED/DRAWN

INSPECTOR

2015 ame:



Vert.


NAVD 88

CONTACT PERSON: Craig Mueller P.E., PROJECT ENGINEER AT 778-7900

INSPECTOR .

OPER. ENGINEER\_


SITE PREP AND GRADING PLAN AT WOODSTOCK INTERSECTION



CREEK BACKFILL PROFILE

# NOTES:

- 1. SEE SHEET 42 FOR CREEK BACKFILL ALIGNMENT.
- CONSTRUCT 4" OF TOP SOIL TYPE B ABOVE FINISHED PROFILE GRADE, THEN SEED, FERTILIZE, AND MULCH, AND INSTALL BIODEGRADABLE EROSION CONTROL BLANKET.







PROJECT ENGINEER CRN


DESIGNED/DRAWN TLW
INSPECTOR

DIR. PUBLIC WORKS TAC
CITY ENGINEER RAR
OPER. ENGINEER

CITY OF BELLINGHAM, WASHINGTON
PUBLIC WORKS DEPARTMENT
ENGINEERING DIVISION

DATUM Job. No.2013-0122 NAD 83/98 Date 04/30/15 NAVD 88 Field Bk.\_\_\_\_

SQUALICUM CREEK RE-ROUTE HABITAT ENHANCEMENT PROJECT JAMES STREET TO IRONGATE GRADING DETAIL AT WOODSTOCK INTERSECTION



Vert. NA

NAVD 88

CONTACT PERSON: Craig Mueller P.E., PROJECT ENGINEER AT 778-7900

DESIGNED/DRAWN

INSPECTOR

CITY ENGINEER\_

OPER. ENGINEER\_

JAMES STREET TO IRONGATE CULVERT BERM DETAILS

44